

WATERLINE FLUSHING AFTER CONSTRUCTION/SYSTEM DISINFECTION WITH DISCHARGE WITH HAUL OFF

1. Preparation

- a. Determine chlorine content of discharged water.
- b. Determine appropriate construction activity for treatment.

2. Process

- a. Flush to tanker for disposal on unpaved construction activity for dust control or compaction.
- b. Confirm that application of water is in appropriate location.

3. Clean-up

- a. Remove equipment from flush point.

4. Documentation

- a. Residual test of discharged water.
- b. Location of water discharged.